


DESCRIPTION FRAME	W8 - WOODEN DOOR OPENING, SINGLE LEAF
CONSTRUCTED DIMENSION	0.97 x 2.35

FRAME

TOTAL	AREA CODE		
	LEVEL 0	LEVEL +1	LEVEL +2

CASING FROM SWEDISH WOOD MEASURING 30X60mm. FINAL SURFACE OF THE WOODEN DOOR PANEL IS PAINTED WITH AN OIL PAINT IN A GREY TINT.

TOTAL PER LEVEL	1		
TOTAL	1		



LAYOUT

FACADE

COMMENTS

- SINGLE LEAF WOODEN DOOR
- FRAMEWORK FROM SOLID BEAMS OF SWEDISH WOOD MEASURING 33X60mm
- FRAMEWORK COVERING, BOTH SIDES WITH A 10mm THICK MDF SHEET
- FINAL SURFACE, PAINTED WITH AN OIL PAINT IN A GREY TINT
- ADJUSTABLE: THREE PIECES PER LEAF
- ACCESSORIES : DOUBLE PIN, STAINLESS STEEL HINGES AND INOX LOCK PER LEAF



PROJECT:  
  
RENOVATION OF ENISA  
OFFICES IN ATHENS

SITE:  
  
VASILISSIS SOFIAS 1,  
MAROUSI -ATHENS

PROJECT ARCHITECT:  
MARIA PARASKEVOPOULOU  
&PARTNERS - ARCHITECTS

ARCHITECTURE  
IMPLEMENTATION  
STUDY

TABLE OF  
WOODEN FRAMES

FRAME CODE:

W8

SCALE:

1:20

TIME OF STUDY:

OCTOBER 2013