


DESCRIPTION FRAME	W13 - WOODEN DOOR OPENING, SINGLE LEAF
CONSTRUCTED DIMENSION	0.97 x 2.45



FRAME	TOTAL	AREA CODE		
		LEVEL 0	LEVEL +1	LEVEL +2
CASING FROM SWEDISH WOOD MEASURING 30X60mm. FINAL SURFACE OF THE WOODEN DOOR PANEL IS PAINTED WITH AN OIL PAINT IN A GREY TINT.	1		1/15	
TOTAL PER LEVEL			1	
TOTAL		1		

COMMENTS

- SINGLE LEAF WOODEN DOOR
- FRAMEWORK FROM SOLID BEAMS OF SWEDISH WOOD MEASURING 33X60mm
- FRAMEWORK COVERING, BOTH SIDES WITH A 10mm THICK MDF SHEET
- FINAL SURFACE, PAINTED WITH AN OIL PAINT IN A GREY TINT
- ADJUSTABLE: THREE PIECES PER LEAF
- ACCESSORIES : DOUBLE PIN, STAINLESS STEEL HINGES AND INOX LOCK PER LEAF



PROJECT:

RENOVATION OF ENISA OFFICES IN ATHENS

SITE:

VASILISSIS SOFIAS 1, MAROUSI -ATHENS

PROJECT ARCHITECT:

MARIA PARASKEVOPOULOU &PARTNERS - ARCHITECTS

ARCHITECTURE IMPLEMENTATION STUDY

TABLE OF WOODEN FRAMES

FRAME CODE:

W13

SCALE:

1:20

TIME OF STUDY:

OCTOBER 2013